



The Right Choice

5305 West 2400 South England Court
West Valley UT, 84120

(801) 892-0500
www.americomtech.com

Project: Tooele County Benson Grist Mill - Drop

Quote # 70596

DATE 3/24/2021
Quotation valid until: 4/8/2021

Company: Tooele County
Contact: Derek Bracken

TOOELE COUNTY CORPORATON
CONTRACT # 21-04-13

SALESPERSON	Email	Mobile	Office
Saxon Neibaur	saxon.neibaur@americomtech.com	801-641-5344	801-892-0519

Scope of Work:

AMERICOM Technology, Inc will identify, locate, and expose all located underground utilities within the running line prior to any excavation or directional drilling activity.

AMERICOM Technology, Inc will be responsible for placing approximately 365' of (1) 1.25" w/MD1 inside by directional drilling method. AMERICOM will also be responsible for setting (1) 24x36x24 hand hole and (1) 13x24x24 hand hole throughout the running line and placing (2) building entrances. AMERICOM will then be responsible for pulling approximately 380' of 24strand microfiber through the newly placed ducts. AMERICOM will then be responsible for splicing (24) strands of fiber and terminating (12) strands of fiber with new equipment in each building. This bid is contingent on AMERICOM being able to get all equipment on site and in position without any restrictions. This bid does not include any permits or permitting fees. This pricing is based off of the AR1416 State of Utah Contract. If all fiber Parts and Materials are installed by AMERICOM and are Corning Products, AMERICOM/Corning will provide a 25 YEAR Warranty per our Corning Certified Installers.

QUANTITY	DESCRIPTION	UNIT PRICE	AMOUNT
1.00	Lump Sum	\$ 20,047.57	\$ 20,047.57
		TOTAL	\$ 20,047.57

Please see contract details on page 2

Comments or Special Instructions:

If you have any questions concerning this quotation, contact Saxon Neibaur.

THANK YOU FOR YOUR BUSINESS!

AMERICOM Technology, Inc will identify, locate, and expose all located underground utilities within the running line prior to any excavation or directional drilling activity.

AMERICOM Technology, Inc will be responsible for placing approximately 365' of (1) 1.25" w/MD1 inside by directional drilling method. AMERICOM will also be responsible for setting (1) 24x36x24 hand hole and (1) 13x24x24 hand hole throughout the running line and placing (2) building entrances. AMERICOM will then be responsible for pulling approximately 380' of 24strand microfiber through the newly placed ducts. AMERICOM will then be responsible for splicing (24) strands of fiber and terminating (12) strands of fiber with new equipment in each building. This bid is contingent on AMERICOM being able to get all equipment on site and in position without any restrictions. This bid does not include any permits or permitting fees. This pricing is based off of the AR1416 State of Utah Contract. If all fiber Parts and Materials are installed by AMERICOM and are Corning Products, AMERICOM/Corning will provide a 25 YEAR Warranty per our Corning Certified Installers.

1. General Conditions

- a) The following table list responsibilities for completion of these items. Those assigned to Americom Technology, Inc. are included in our quoted price below. Those assigned to Customer are not included in the pricing below, but may be added at an additional price.
- b) Americom will be allowed to work 10-hour days 6 days per week.
- c) Customer to provide ample work space for equipment.
- d) Clear access to work areas for the duration of the project.

Customer	Americom	Description of Task Assignments
	x	Provide Engineering Drawings
	x	Provide Geotechnical Information
	x	Dig Permits
	x	Easement and Right of Ways
	x	Point of contact for this project
	NA	Rail Road Permit
	x	Call for Public Utility Locates
x		Private Property Utilities Locate
	x	Expose Existing Public Utilities
	x	Expose Existing Private Utilities
	x	Provide Entry and Exit Pits for Directional Drilling
	x	Order and provide inspections
	x	Safety Meeting and Job Box Meetings
	x	Provide Access to Water for Mixing of Drill Fluids
	x	Provide Disposal of Drill Fluids and Spoil Material
	x	Provide Conduit/Duct and Other Associated Materials
	X	Restoration of Surfaces
x		Final Clean and As-Builds/ Surveys
	x	Traffic Control

2. Rock Clause / Attempt Fees: It is assumed that the area for the placement of the conduits using directional drilling methods is free of cobble, rock, and other obstacles so that the soil is drillable. The pricing provided in this quote is based on clay or sand loam type soils. If in the process of potholing or directional drilling it is determined that the soil conditions are cobble, rocky or have obstruction, Americom will need to charge additional Rock pricing. Rock pricing will be applied to the full length of the HDD. Americom will charge a day rate for each directional drilling attempt. The price per day for unsuccessful attempt is \$5,000. Attempt fees and or additional rock cost would need to be approved by Customer and Americom Technology, Inc. prior to engaging in any rock shot attempt.

3. Utility Locating / Potholing: For the safety of the general public, Customer and Americom Technology, Inc. all underground utilities must be identified, located, and exposed prior to any excavation or directional drilling activity. Customer must provide information on all private utilities to Americom Technology, Inc. Americom Technology, Inc. will order the Blue Staking of the Public Utilities and obtain the correct Blue Stake Locate work order number. All utilities must be exposed after the Blue Staking is completed. Blue Staking will only provide the approximate location of the utilities on the surface of the ground. The elevation of those utilities must be determined by exposing the utility. This can be accomplished by use of hand digging or hydro-excavation methods. Once the utilities are located and exposed the correct directional drill or excavation path can be determined based on the location and depth of the utilities.

4. Exclusion / Standby: Any work and/or material that are not specifically defined in this proposal are excluded. (Any additions or changes in quantities outside the scope of this project will be considered a change order request.) In the event Americom Technology, Inc. is delayed at any time during the course of the project due to changes to the scope of work, unusual delays, or environmental challenges, Americom Technology, Inc. will immediately cease to perform further services in support of this project. Customer and Americom Technology, Inc. shall take all reasonable steps to minimize the incurrence of costs allocable to the work covered by this project during the period of work stoppage.

(Standby charges shall be charged at a rate of \$500.00 per hour to a maximum of \$5,000.00 per day)

THE INFORMATION CONTAINED IN THIS PROPOSAL IS FOR THE EXCLUSIVE USE OF CUSTOMER AND IS NOT TO BE RELEASED WITHOUT PRIOR WRITTEN CONSENT FROM AMERICOM TECHNOLOGY INC.

PRICING GUARANTEE PERIOD

15 Days

TAX

All applicable state, local and federal taxes have been included unless otherwise noted.

RESTOCKING CHARGE

There will be a 20% charge on material that must be restocked due to any changes on the part of customer. Items must be in original packaging and undamaged.

PAYMENT TERMS - SUBJECT TO CREDIT APPROVAL

Payment due upon receipt of invoice. Finance charge of 1 1/2% per month, which is an annual percentage rate of 18%, will be added to all invoices not paid within 30 days of invoice date which will be invoiced at completion of project.

"I, the undersigned, hereby agree that in the event of default in the payment of any amount due, and if this account is placed in the hands of an agency or attorney for collection or legal action, to pay all costs of collection including a reasonable collection agency and/or attorney's fee, and costs of court incurred and permitted by laws governing these transactions, and further agree to the jurisdiction in the appropriate courts in Salt Lake County, in the State of Utah.

CUSTOMER ACCEPTANCE:
SIGNED: [Signature] DATE: 23 April 2021
PRINTED NAME: Tam Kemp P.O.#: _____

ATTEST:
[Signature]
MARILYN K. GILLETTE
TOOELE COUNTY CLERK

